

AFRL-ML-WP-TR-1998-4212

**B-1 AIRCRAFT MAIN HYDRAULIC
PUMP TESTS WITH MIL-H-87257
HYDRAULIC FLUID**



Shashi K. Sharma Carl E. Snyder, Jr
Lois J. Gschwender Gregory J. Cecere
Materials and Manufacturing Directorate

Ronald Mortimer
University of Dayton Research Institute
Dayton, Ohio

JUNE 1998

FINAL REPORT FOR PERIOD JUNE 1 1992 – SEPTEMBER 30, 1993

Approved for public release; distribution unlimited

19990218031

DTIC QUALITY INSPECTED 4

**MATERIALS & MANUFACTURING DIRECTORATE
AIR FORCE RESEARCH LABORATORY
AIR FORCE MATERIEL COMMAND
WRIGHT-PATTERSON AIR FORCE BASE, OH 45433-7734**

NOTICE


Using government drawings, specifications, or other data included in this document for any purpose other than government procurement does not in any way obligate the US government. The fact that the government formulated or supplied the drawings, specifications, or other data does not license the holder or any other person or corporation; or convey any rights or permission to manufacture, use, or sell any patented invention that may relate to them.

This report is releasable to the national technical information service (NTIS). At NTIS, it will be available to the general public, including foreign nations.


This technical report has been reviewed and is approved for publication.



SHASHI K. SHARMA, Project Engineer
Nonstructural materials Branch
Nonmetallic Materials Division



WAYNE E. WARD, Chief
Nonstructural materials Branch
Nonmetallic Materials Division



ROBERT L. RAPSON, Chief
Nonmetallic Materials Division
Materials and Manufacturing Directorate

If your address has changed, if you wish to be removed from our mailing list, or if the addressee is no longer employed by your organization please notify AFRL/MLBT, 2941 P Street, Suite 1, Wright-Patterson AFB OH 45433-7750 to help maintain a current mailing list.

Do not return copies of this report unless contractual obligations or notice on a specific document requires its return.

REPORT DOCUMENTATION PAGE			Form Approved OMB No. 0704-0188	
Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.				
1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE June 1998		3. REPORT TYPE AND DATES COVERED Final 1992-1993
4. TITLE AND SUBTITLE B-1 Aircraft Main Hydraulic Pump Tests With MIL-H-87257 Hydraulic Fluid			5. FUNDING NUMBERS C: F33615-90-C-5963 PE: 624347 PR: 4347 TA: WD WU: 51	
6. AUTHOR(S) Shashi K. Sharma, Carl E. Snyder, Jr., Lois J. Gschwender and Gregory J. Cecere, Materials and Manufacturing Directorate, WPAFB, Ohio; Ronald Mortimer, University of Dayton Research Institute, Dayton, Ohio				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) AFRL/MLBT 2941 P Street Suite 1 Wright-Patterson Air Force Base, OH 45433-7750			8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) Materials & Manufacturing Directorate Air Force Research Laboratory Air Force Materiel Command Wright-Patterson Air Force Base, Oh 45433-7734 POC: Shashi K Sharma, AFRL/MLBT, 937-255-9029			10. SPONSORING/MONITORING AGENCY REPORT NUMBER AFRL-ML-WP-TR-1998-4212	
11. SUPPLEMENTARY NOTES				
12a. DISTRIBUTION AVAILABILITY STATEMENT Approved for public release, distribution unlimited			12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words) In an effort to convert the B-1 aircraft from MIL-H-5606 to the fire resistant MIL-H-87257 hydraulic fluid, the Air Force sponsored a study conducted by Rockwell International from April 1992 through June 1992 under contract F34601-89-C-0401. The results of this study are published in Rockwell Report NA-91-1598, date 17 June 1992. As part of this study, two pump tests were conducted by Vickers using B-1 aircraft hydraulic pumps (Vickers PV3-300-7B) and MIL-H-87257 (ROYCO 777) hydraulic fluid. During the first test, the pump failed prematurely. The second test was stopped before the scheduled test duration because some metal was observed in the filter patch test. Due to lack of funding, no additional pump tests were carried out to check the compatibility of MIL-H-87257 and the B-1 hydraulic pumps. This being the only unresolved issue standing in the way of transitioning the MIL-H-87257 fluid to the B-1 aircraft, the Nonstructural Materials Branch of the Materials and Manufacturing Directorate of Air Force Research Laboratory (AFRL/MLBT) undertook in-house pump tests with B-1 hydraulic pumps to provide the necessary data. A base line test was conducted using MIL-H-5606 and a second test was run under identical conditions using MIL-H-87257. Both pump tests were successful. Based on these tests MIL-H-87257 was deemed suitable for use in B-1 aircraft. The results of the pump tests are the subject of this report.				
14. SUBJECT TERMS			15. NUMBER OF PAGES 78	
			16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT Unclassified	18. SECURITY CLASSIFICATION OF THIS PAGE Unclassified	19. SECURITY CLASSIFICATION OF ABSTRACT Unclassified	20. LIMITATION OF ABSTRACT SAR	

TABLE OF CONTENTS

Section	Page
1.0 INTRODUCTION.....	1
2.0 TEST OBJECTIVE.....	1
3.0 PUMP TESTS	1
3.1 Pump Test Plan	1
3.2 Hydraulic Pump Test Stand Modifications	2
3.3 Pump Tests.....	3
3.4 Analyses of Fluid Samples	4
4.0 CONCLUSIONS	5
5.0 REFERENCES	5
6.0 FIGURES	
1 Hydraulic Pump Test Stand Configurations	6
2 Hydraulic Pump Test Circuit	7
3 Case Drain Flow in B-1 Pump Tests	8
4 Viscosity Loss in B-1 Pump Tests	9
5 Four-Ball Wear Scar with B-1 Pump Test Fluid Samples	10
7.0 TABLES	
1 Water Content and Acid Numbers of Pump Test Fluid Samples	11
2 Trace Metal Analyses of Pump Test Fluid Samples	12
8.0 APPENDICES	
APPENDIX A: Inspection Photographs from Pump Test 33, MIL-H-5606F	
APPENDIX B: Inspection Photographs from Pump Test 34, MIL-H-87257	
APPENDIX C: Raw Data for Pump Test 33 with MIL-H-5606F	
APPENDIX D: Raw Data for Pump Test 34 with MIL-H-87257	

1.0 INTRODUCTION

MIL-H-83282 is a synthetic, less flammable hydraulic fluid that replaced the flammable MIL-H-5606 hydraulic fluid in most Air Force aircraft. MIL-H-83282 does not meet the viscosity requirements for -65 °F operation. However, MIL-H-87257, the low temperature version of MIL-H-83282 fluid, does meet these requirements.

In an effort to convert the B-1 aircraft from MIL-H-5606 to MIL-H-87257, the Air Force sponsored a study conducted by Rockwell International from April 1991 through June 1992, under contract F34601-89-C-0401. The results of this study are published in Rockwell Report NA-91-1598, dated 17 June 1992. As part of this study, two pump tests were conducted by Vickers using B-1 aircraft hydraulic pumps (Vickers PV3-300-7B) and MIL-H-87257 (ROYCO 777) hydraulic fluid. During the first test, the pump failed prematurely. The second test was stopped before the scheduled test duration because some metal was observed in the filter patch-test. Due to lack of funding no additional pump tests were carried out to check the compatibility of MIL-H-87257 and B-1 hydraulic pumps. This being the only unresolved issue standing in the way of transitioning this fluid to the B-1 aircraft, the Nonstructural Materials Branch of the Materials Directorate of Wright Laboratory (WL/MLBT) decided to conduct in-house pump tests with MIL-H-87257 and B-1 hydraulic pumps to provide the necessary data. The results of the two pump tests carried out at WL/MLBT are the subject of this report.

2.0 TEST OBJECTIVE

The objective of this program was to complete the initial studies begun by Rockwell to determine the compatibility of MIL-H-87257 with the B-1 hydraulic pumps.

3.0 PUMP TESTS

The Vickers PV3-300-7B hydraulic pump is a constant pressure, variable displacement pump capable of very high flow rates of up to 64 gpm and requiring high horsepower input. Due to the horsepower limitations of the WL/MLBT hydraulic pump test stand, it was not practical to duplicate either the qualifying tests or the tests conducted at Vickers. After reviewing the test conditions and the pump failure modes generated at Vickers during the hydraulic pump testing of MIL-H-87257 hydraulic fluid, the following plan was agreed upon by all the interested organizations.

3.1 PUMP TEST PLAN

Hydraulic Pump: Vickers Model PV3-300-7B Pump (new pump for each test).

Test Fluids: MIL-H-5606F, Baseline, WL/MLBT Pump Test 33
MIL-H-87257 (ROYCO 777), WL/MLBT Pump Test 34

Test Duration: Total 90 hours.

STAGE I: 30 hours
STAGE II: 30 hours
STAGE III: 30 hours

Pump Inlet Pressure: 95-100 psig.
Pump Outlet Pressure: 4150 psig.
Pump Outlet Flow: 50 gpm.
Pump Shaft Speed: 5250 rpm.

Pump Inlet Temperature:	STAGE I: 180 °F STAGE II: 210 °F STAGE III: 250 °F
Filter Elements:	Main Filter - Pall Corporation, P/N AC-9516F-1, 3 micron, replaced after each test Heat Exchanger Bypass Filter - Pall Corporation P/N AC-7031F-1297Y6, 5 micron, replaced after each test Case Drain Filter - Pall Corporation P/N AC-7031F-1297, 5 micron, replaced after each test Patch Filter - Millipore (housing P/N XX047-00, element P/N LSWP-047-00), 5 micron, inspected and replaced after each stage
Fluid Samples:	Taken at approximately 0, 6, 15, and 30 hours of each stage
Pump Disassembly and Inspection:	Pretest and after each stage

3.2 HYDRAULIC PUMP TEST STAND MODIFICATIONS

The existing pump test stand at WL/MLBT was designed primarily for testing new and experimental hydraulic fluids using small to medium displacement aircraft hydraulic pumps operating at low flow rates. The PV3-300-7B is a large displacement pump, which would be operated at high flow rates during these tests. To accommodate these flow rates, an increase in power, tubing size, filter capacity and heat exchanger capacity was necessary. The modified test circuit is shown in figure 1. The variable speed drive motor on the existing test stand would supply the additional power needed as it would produce 150 hp versus the approximate 145 hp the pump required at the test plan flow rate of 50 gpm. In order to satisfy the other requirements, major changes to the pump test stand were necessary. The hydraulic circuits of the existing test stand were altered in the following manner:

a. High pressure flow (pump outlet) - To accommodate the higher pressure and flow rate from the pump this circuit was rebuilt using larger tubing size. The throttling valve was modified using an upgrade kit. A circuit was also added to bypass this valve. The relief valve was upgraded and re-calibrated. The sensors remained unchanged.

b. Case drain flow - What had been the main return hydraulic circuit was modified to serve as the new case drain circuit. The same heat exchanger, filter assembly, flow meter and other sensors were utilized. Several valves and additional sensors were also incorporated into this circuit for temperature-pressure indication and control.

c. Main return flow (pump inlet) - An entirely new circuit was designed and fabricated. Downstream of the throttle valve the new main return flow was split into two similar circuits. The flow through these circuits passed through individual heat exchangers and filters before being rejoined. Also, at this junction the flow from the heat exchanger bypass circuit was added with the combined flow subsequently passing through a new high capacity flow meter. Case drain flow and any needed make-up fluid from the reservoir were then added to the return flow. Further downstream were several sensors and a sampling valve before connection to the pump inlet.

To accomplish these changes and other necessary modifications to the test stand, the following major items were designed, fabricated, purchased or otherwise obtained:

a. A new pump mounting flange and drive spline were designed and fabricated with the help of necessary installation drawings furnished by Vickers Corporation.

b. New hydraulic fittings which mate with the pump inlet-outlet and which also use the same spring energized seals as on the aircraft were designed and fabricated. An adapter was purchased for the Rosan fitting on the pump case drain.

c. New throttle valve parts were purchased to upgrade this valve.

d. Two large (3' long x 8" diameter) heat exchangers were purchased. The large size heat exchangers were needed for the 180 °F inlet temperature requirement for Stage I.

e. Two large capacity filter assemblies including elements were graciously provided by Pall Corporation.

f. A new high capacity cooling system recirculating pump, associated fittings and hoses were purchased. Modification to the cooling systems reservoir was also made to accommodate this new pump.

After all these changes were accomplished, the test stand required approximately 8 gallons of test fluid to fill, the majority of it being in the heat exchangers and filters. During operation, approximately 7 gallons of fluid circulated. A schematic of the entire B-1 hydraulic pump test circuit is shown in Figure 2.

3.3 PUMP TESTS

The WL/MLBT hydraulic pump test stand is computer controlled with automatic shutdown interlocks. Data obtained during testing is presented digitally and simultaneously recorded on strip charts.

During these tests, pump stand start up was accomplished in the following manner. After proper pump test stand preparation, the pump depressurizing circuit was energized which allowed the drive motor and the pump speed to be increased at lower pump outlet pressures. After a few seconds and at around 5000 rpm, this circuit was de-energized allowing the outlet pressure to increase to normal levels. The speed was then increased to 5250 rpm, followed by a gradual increase of the output flow from the startup value of 3 gpm to 50 gpm. The pump inlet temperature was maintained at the desired value and the test continued for the entire 30 hour stage duration.

3.3.1 PUMP TESTS 33 AND 34

The MIL-H-5606F testing was conducted as outlined in Section II except that the pretest pump disassembly and inspection before the start of Stage I was not conducted. This pump was installed on the test stand in order to verify proper operation of the modified test stand. During this verification process, and filling the stand with fresh MIL-H-5606F, approximately 12 operating hours were accumulated on the pump, of which very few were at high flow rates or at high fluid temperature. It was then decided to continue using this pump for Test 33 without removing it from the stand for pretest inspection. During inspection after Stage I completion, a slight anomaly was observed on the rubbing surfaces of the piston shoes - radial erosion lines across the shoe faces. Unfortunately, since there was no pump inspection before the beginning of Stage I there is no way to determine if these lines were generated during pump stand operation verification, Stage I testing or were there to begin with. This condition did not seem to affect the performance of the pump. The subsequent pump inspections after Stage II and III revealed little or no change in the appearance of these lines. With the exception of these radial lines, the disassembly and inspection of the pump after each stage completion showed only slight polishing wear with no signs

of loose material or debris. No evidence of cavitation on any pump parts was observed. Overall, the pump and the test fluid performed well during this test. No adjustments were made to the pump compensator before or during this test. Inspection of the patch filter after each stage completion revealed nothing unusual. No significant leaks were observed from the test stand. A total of about 500 ml of fluid leaked from the pump shaft seal. After completion of this test the great majority of the fluid was drained from the tubing, filter assemblies, reservoir and heat exchangers. Some of the tubing, the filter bowls and both large heat exchangers were removed from the stand and drained. The heat exchangers were partially disassembled to facilitate the draining process.

Pump Test 34 with MIL-H-87257 fluid was also conducted as outlined in Section II. Again, the pump and test fluid performed well. There were no discrepancies observed during pump inspections which were conducted after the completion of each stage. There were no signs of any loose material or debris, and only some slight polishing wear was observed on most rubbing surfaces. No evidence of cavitation on any pump part was observed. No adjustments were made to the pump compensator before or during this test. Inspection of the patch filter revealed nothing unusual. No significant leaks were observed from the test stand. A total of 115 ml of fluid leaked from the pump shaft seal.

Photographs of all critical pump parts and surfaces were taken during the pump inspections. These photos are presented in Appendix A and B. Detailed video movies were made during each disassembly and inspection, and are available for loan from WL/MLBT (point of contact: Shashi K. Sharma, at (937) 255-9029).

The pump case drain flow rates were observed and recorded during both pump tests. A comparison plot of the data is shown in Figure 3. It is interesting to note the case drain flow rates for the MIL-H-5606F fluid start out lower, but end up at a higher rate when compared to the flow rates for MIL-H-87257 fluid. This is attributed to the loss of viscosity of MIL-H-5606 with time due to its shear instability, discussed later.

The bleeding of air from the test stand was more difficult in the case of MIL-H-5606 as it seemed to retain more air than MIL-H-87257.

3.4 ANALYSIS OF FLUID SAMPLES

During the pump tests, fluid samples were extracted from the operating test stand as the testing progressed. These samples were taken at the approximate intervals listed in Section II. A number of different analyses were conducted on these samples.

The viscosities of the fluid samples taken were determined at 40 °C and 100 °C. These viscosities are compared in Figure 4. It is easily seen that MIL-H-5606F suffered significant viscosity losses during the first 30 hours of pump testing, whereas the viscosity of MIL-H-87257 was very stable throughout the test. The viscosity index (VI) improvers used to boost the viscosity of MIL-H-5606, break-up under the high shear environment inside the pump, causing a permanent loss of the fluid viscosity. Under the high pressure and high shear rate environment, the VI improved fluids behave more like the base oil (Reference 1).

Water content and acid numbers of the fluid samples were determined and are shown in Table 1.

Trace metal analysis was also performed on these fluid samples. The samples were analyzed for 19 elements including Fe, Ag, Cr, Cu, Mg, Na, Ni, Pb, Si, Sn, Ti, B, Ba, Cd, Mn, Mo, V, and Z. Only those elements which show concentrations above 0.1 ppm. are reported in Table 2.

Samples taken at the end of each stage of testing and the fresh samples of each of the test fluids were evaluated for lubricity. These evaluations were accomplished by 4-ball wear testing method (ASTM D-

4172). The results of the lubricity tests are shown in Figure 5. Clearly, these data indicate better lubricity for MIL-H-87257 when compared to MIL-H-5606F.

4.0 CONCLUSIONS

4.1 MIL-H-5606 and MIL-H-87257 hydraulic fluids were successfully pump tested in B-1 aircraft hydraulic pumps under identical conditions. Both pumps showed only slight polishing wear with the exception of the appearance of radial lines on the piston shoe faces of the pump tested with MIL-H-5606. It could not be concluded whether these lines appeared during the testing, or existed prior to the test. However, these lines did not seem to affect the functioning of the pump, and also did not grow in size during the test. No cavitation on any pump parts was observed for both tests.

4.2 MIL-H-87257 exhibited better lubricity than MIL-H-5606, as determined by the ASTM D-4172 four-ball wear tests.

4.3 Viscosity of MIL-H-5606 reduced by 50% during the first 30 hours of testing.

4.4 MIL-H-5606 seems to retain more air than MIL-H-87257.

4.5 MIL-H-87257 has exhibited equivalent or better performance than MIL-H-5606 in the B-1 hydraulic pump tests.

5.0 REFERENCES

1. Sharma, S.K. and Forster, N.H., and Gschwender, L.J., "Effect of Viscosity Index Improvers on the Elastohydrodynamic Lubrication Characteristics of a Chlorotrifluoroethylene and a Polyalphaolefin Fluid," Tribology Transactions, vol. 36, no. 3, pp 555-564, Oct 1993

6.0 FIGURES




Figure 1. Hydraulic Pump Test Stand Configurations




Figure 2. B-1 Hydraulic Pump Test Circuit




Figure 3. Case drain flow in B-1 pump tests




Figure 4. Viscosity change in B-1 pump tests




Figure 5. Four-Ball Wear Scar with B-1
Pump Test Fluid Samples

7.0 TABLES

TABLE 1. WATER CONTENT AND ACID NUMBERS OF MIL-H-5606F

SAMPLE NUMBER	TOTAL HOURS	STAGE HOURS	WATER (ppm)	ACID NO. (mgKOH/gm)
STAGE-I				
FRESH FLUID	0.0	0.0	56	0.00
MLO 93-1	12.2	0.2	55	0.00
MLO 93-2	18.0	6.0	57	*
MLO 93-3	27.5	15.5	*	*
MLO 93-4	42.5	30.0	94	0.00
STAGE-II				
MLO 93-5	44.2	1.0	89	0.00
MLO 93-6	49.5	6.3	*	*
MLO 93-7	58.3	15.1	*	*
MLO 93-8	73.2	30.0	116	0.08
STAGE-III				
MLO 93-9	76.6	0.2	92	0.00
MLO 93-10	82.7	6.0	*	*
MLO 93-11	91.4	15.0	*	*
MLO 93-12	106.0	29.6	90	0.00
MLO 93-13 (case line)	106.0	29.6	116	0.00
MLO 93-14 (pump case)	106.0	29.6	97	*

* data not determined

WATER CONTENT AND ACID NUMBERS OF MIL-H-87257

SAMPLE NUMBER	TOTAL HOURS	STAGE HOURS	WATER (ppm)	ACID NO. (mgKOH/gm)
STAGE-I				
FRESH FLUID	0.0	0.0	85	0.04
MLO 93-66	0.1	0.1	127	0.00
MLO 93-15	6.1	6.1	172	*
MLO 93-16	15.3	15.3	169	*
MLO 93-67	30.3	30.3	168	*
STAGE-II				
MLO 93-68	30.8	0.5	166	0.00
MLO 93-69	36.3	6.0	*	*
MLO 93-70	45.4	15.1	*	*
MLO 93-71	60.3	30.0	173	0.00
STAGE-III				
MLO 93-72	60.9	0.6	165	0.00
MLO 93-73	66.7	6.0	*	*
MLO 93-74	78.8	15.0	*	*
MLO 93-75	93.8	30.0	154	0.00

* data not determined

Table 2. Trace Metal Analysis of Pump Test Fluid Samples

Test 33 with MIL-H-5606F


Sample Number	Total Hours	Stage Hours	Fe (ppm)	Ba (ppm)
Stage I				
MLO 93-1	12.2	0.2	0.00	1.7
MLO 93-2	18.0	6.0	0.12	1.9
MLO 93-3	27.5	15.5	0.16	1.9
MLO 93-4	42.5	30.0	0.26	2.0
Stage II				
MLO 93-5	44.2	1.0	0.22	1.5
MLO 93-6	49.5	6.3	0.26	1.7
MLO 93-7	58.3	15.1	0.31	1.8
MLO 93-8	73.2	30.0	0.39	1.8
Stage III				
MLO 93-9	76.6	0.2	0.27	1.5
MLO 93-10	82.7	6.0	0.32	1.5
MLO 93-11	91.4	15.0	0.33	1.6
MLO 93-12	106.0	29.6	0.35	1.5
MLO 93-13 (case line)	106.0	29.6	0.41	1.5
MLO 93-14 (pump case)	106.0	29.6	0.49	1.6

Test 34 with MIL-H-87257


Sample Number	Total Hours	Stage Hours	Fe (ppm)	Ba (ppm)
Stage I				
MLO 93-66	0.1	0.1	0.13	3.1
MLO 93-15	6.1	6.1	0.02	2.4
MLO 93-16	15.3	15.3	0.04	2.3
MLO 93-67	30.3	30.3	0.05	2.3
Stage II				
MLO 93-68	30.8	0.5	0.04	2.3
MLO 93-69	36.3	6.0	0.05	2.2
MLO 93-70	45.4	15.1	0.05	2.2
MLO 93-71	60.3	30.0	0.06	2.1
Stage III				
MLO 93-72	60.9	0.6	0.07	2.1
MLO 93-73	66.7	6.0	0.07	1.9
MLO 93-74	78.8	15.0	0.06	1.9
MLO 93-75	93.8	30.0	0.08	1.6

Appendix A


Inspection Photographs from
Pump Test 33, MIL-H-5606F



Stage I




Stage II




Stage III


Piston 1 Shoe Face After Stages I, II, and III
Pump Test 33 with MIL-H-5606F



Stage I




Stage II




Stage III


Piston 2 Shoe Face After Stages I, II, and III
Pump Test 33 with MIL-H-5606F



Stage I




Stage II




Stage III


Piston 3 Shoe Face After Stages I, II, and III
Pump Test 33 with MIL-H-5606F



Stage I




Stage II




Stage III


Piston 4 Shoe Face After Stages I, II, and III
Pump Test 33 with MIL-H-5606F



Stage I



Stage II




Stage III


Piston 5 Shoe Face After Stages I, II, and III
Pump Test 33 with MIL-H-5606F



Stage I




Stage II



Stage III


Piston 6 Shoe Face After Stages I, II, and III
Pump Test 33 with MIL-H-5606F



Stage I




Stage II




Stage III


Piston 7 Shoe Face After Stages I, II, and III
Pump Test 33 with MIL-H-5606F



Stage I




Stage II




Stage III


Piston 8 Shoe Face After Stages I, II, and III
Pump Test 33 with MIL-H-5606F



Stage I




Stage II




Stage III


Piston 9 Shoe Face After Stages I, II, and III
Pump Test 33 with MIL-H-5606F



Stage I




Stage II




Stage III


Hold Down Plate - Non Rubbing Side after Stage I, II and III
Pump Test 33 with MIL-H-5606F



Stage I




Stage II




Stage III


Hold Down Plate - Rubbing Side after Stage I, II and III
Pump Test 33 with MIL-H-5606F



Stage I




Stage II




Stage III

Cylinder Block Face after Stage I, II and III
Pump Test 33 with MIL-H-5606F




Stage II




Stage III

Waffle Plate - Rubbing Side after Stage II and III
Pump Test 33 with MIL-H-5606F



Stage II




Stage III


Waffle Plate - Non Rubbing Side after Stage II and III
Pump Test 33 with MIL-H-5606F



Stage I




Stage II




Stage III

Cylinder Block Plate after Stage I, II and III
Pump Test 33 with MIL-H-5606F



Stage I



Stage II




Stage III

Actuator Piston - Front View after Stage I, II and III
Pump Test 33 with MIL-H-5606F




Stage II



Stage III


Actuator Piston -Side view after Stage II and III
Pump Test 33 with MIL-H-5606F



Housing after Stage I
Pump Test 33 with MIL-H-5606F




Stage II



Stage III

Housing after Stage II and III
Pump Test 33 with MIL-H-5606F




Partial Assembly of Test Pump after Stage II
Pump Test 33 with MIL-H-5606F


Appendix B

Inspection Photographs from


Pump Test 34, MIL-H-87257




Pretest



Stage I




Stage II



Stage III


Piston 1 Shoe Face at Pretest, and After Stages I, II, and III
Pump Test 34 with MIL-H-87257




Pretest



Stage I




Stage II




Stage III


Piston 2 Shoe Face at Pretest, and After Stages I, II, and III
Pump Test 34 with MIL-H-87257




Pretest



Stage I



Stage II




Stage III


Piston 3 Shoe Face at Pretest, and After Stages I, II, and III
Pump Test 34 with MIL-H-87257




Pretest



Stage I




Stage II




Stage III


Piston 4 Shoe Face at Pretest, and After Stages I, II, and III
Pump Test 34 with MIL-H-87257




Pretest



Stage I




Stage II




Stage III


Piston 5 Shoe Face at Pretest, and After Stages I, II, and III
Pump Test 34 with MIL-H-87257




Pretest



Stage I




Stage II




Stage III


Piston 6 Shoe Face at Pretest, and After Stages I, II, and III
 Pump Test 34 with MIL-H-87257




Pretest



Stage I




Stage II




Stage III


Piston 7 Shoe Face at Pretest, and After Stages I, II, and III
Pump Test 34 with MIL-H-87257




Pretest



Stage I




Stage II




Stage III


Piston 8 Shoe Face at Pretest, and After Stages I, II, and III
Pump Test 34 with MIL-H-87257




Pretest



Stage I




Stage II




Stage III


Piston 9 Shoe Face at Pretest, and After Stages I, II, and III
Pump Test 34 with MIL-H-87257



Stage I




Stage II




Stage III


Hold Down Plate - Non Rubbing Side after Stage I, II, and III
Pump Test 34 with MIL-H-87257



Stage I




Stage II




Stage III


Hold Down Plate - Rubbing Side after Stage I, II, and III
Pump Test 34 with MIL-H-87257




Pretest



Stage I




Stage II




Stage III

Cylinder Block Face at Pretest and after Stage I, II, and III
Pump Test 34 with MIL-H-87257




Stage I




Stage II

Waffle Plate - Rubbing Side after Stage I and II
Pump Test 34 with MIL-H-87257




Stage I




Stage II

Waffle Plate - Non Rubbing Side after Stage I and II
Pump Test 34 with MIL-H-87257



Stage I

Stage II




Stage III

Cylinder Block Plate after Stage I, II, and III
Pump Test 34 with MIL-H-87257




Pretest



Stage I




Stage II



Stage III


Actuator Piston - Front View at Pretest and after Stage I, II, and III
Pump Test 34 with MIL-H-87257




Pretest



Stage I




Stage II




Stage III

Actuator Piston - Side View at Pretest and after Stage I, II, and III
Pump Test 34 with MIL-H-87257




Pretest



Stage I

Housing at Pretest and after Stage I
Pump Test 34 with MIL-H-87257




Stage II



Stage III

Housing after Stage II and III
Pump Test 34 with MIL-H-87257



Partial Assembly of Test Pump at Pretest
Pump Test 34 with MIL-H-87257

Appendix C

Raw Data for Pump Test 33

with MIL-H-5606F

PUMP TEST NO. 33

TEST FLUID:

PUMP TEST DATA FOR AIRCRAFT HYDRAULIC FLUID
WJMLBT, WPAFB PUMP TEST STAND NO. 1

MIL-H-5606F
MLO 92-144

TEST PUMP: MODEL Vickers PV3-300-7B
S/N : MX 480659B

A= Throttling Valve Open

B= Throttling Valve Closed

Date	Time	Test Cell Temp. (F)	Test Hrs. (as on the counter)	Total Flow (Gallons)		Reserv. Fluid Level (mm)	Total Seal Leakage (ml)	Speed (RPM)		Torque (in-lb)		Motor Current (amps)		Pressure Drop (PSI)				Pump Inlet Pressure (psig)		Pump Outlet Pressure (psig)	
				Main	Case			A	B	A	B	A	B	Main Filter 1	Case Filter	Case Filter	Case Filter	A	B	A	B
6-Jan-93	0905	65	12.0	0	0																
6-Jan-93	0917		12.2																		
6-Jan-93	1147		14.7																		
7-Jan-93	0835	65	14.7																		
7-Jan-93	0850	65	14.9																		
7-Jan-93	1025	77	16.3	10,808	706			5,220		1752		164		26			4	92		4,136	
7-Jan-93	1205	80	18.0																		
7-Jan-93	1305	80	19.0	18,953	1,244	131.56		5,220		1759		163		26		3.6	71	93		4,137	
7-Jan-93	1505	72	21.0	24,956	1,646	131.56		5,220		1759		163		25		3.5	68	94		4,137	
7-Jan-93	1825	71	24.3	34,914	2,322	131.56		5,220		1734		163		25		3.8	68	95		4,140	
7-Jan-93	2140	69	27.5	44,745	2,996	131.30		5,220		1745		163		25		3.9	68	96		4,140	
7-Jan-93	2140	69	27.5																		
8-Jan-93	0115	73	31.2	55,429	3,736	131.40		5,218		1752		163		25		4.1	69	95		4,137	
8-Jan-93	0400	72	33.9	63,681	4,296	131.40		5,219		1752		162		25		4.2	68	93		4,134	
8-Jan-93	0648		36.6																		
8-Jan-93	0705		36.6																		
8-Jan-93	0825	79	38.0	75,658	5,106	131.40		5,208		1743		162		25		4.2	68	91		4,132	
8-Jan-93	1100	80	40.5	83,287	5,620	131.40		5,210		1750		162		25		4.3	69	92		4,131	
8-Jan-93	1220	80	42.0	87,500	5,908	131.37		5,210		1746		162		25		4.3	69	90		4,130	
8-Jan-93	1245		42.4				250														
8-Jan-93	1250		42.5	89,034	6,012																
28-Jan-93	1445		43.2																		
28-Jan-93	1545		44.2																		
28-Jan-93	1615	82	44.7	94,746	6,406	131.50		5,215		1730		161		26		4.1	77	94		4,111	
28-Jan-93	1700	82	45.5	97,037	6,564	131.50	270	5,215		1718		160		25		4.0	78	92		4,106	
28-Jan-93	1937	80	48.1	104,924	7,128	131.50	320	5,218		1708				24		3.9	79	91		4,102	
28-Jan-93	2100		49.5																		
29-Jan-93	0040	83	53.1	119,760	8,224	131.30	330	5,217		1767		163		26		4.0	75	7		4,108	
29-Jan-93	0338	82	56.1	128,843	8,892	131.30	340	5,217		1733		161		25		3.9	75	7		4,104	
29-Jan-93	0522	86	57.9	134,120	9,292	131.30	350	5,218		1710		159		24		3.8	77	8		4,106	
29-Jan-93	0550		58.3																		
29-Jan-93	0700		59.5	138,920																	
29-Jan-93	0730	84	60.0	140,419	9,768	131.20	360	5,215		1709		159		25		3.8	78	7		4,105	
29-Jan-93	0930	87	62.0	146,419	10,216	131.20	370	5,215		1721		160		25		3.7	78	8		4,107	

* (100-200 ml of 5606 had accumulated inside of pump mounting flange + overboard flow through sensor.

(Seal leakage collection in beaker started @ start of Stage II.)

which = approx. 250 ml.)

* Static Reading (Offset) : During Stage I & Stage II = 3.0 psi.; Before Stage III = 2.6 psi.; After Stage III = 0.1 psi.

** Static Reading (Offset) During the Whole Test = -7.0 psi.

*** Static Reading (Offset) During the Whole Test = -4.0 psi.

PUMP TEST NO. 33

TEST PUMP : MODEL Vickers PV3-300-7B										PUMP TEST DATA FOR AIRCRAFT HYDRAULIC FLUID										TEST FLUID :	
SN: MX 490659B										WU/MLBT, WPAFB PUMP TEST STAND NO. 1										MIL- H-5606F MLO 92-144	
A- Throttling Valve Open B- Throttling Valve Closed																					
Test Hrs.	Coolant Flow (GPM)		Flow Rate (GPM)				Fluid Temperature (F)						Coolant Temperature (F)				REMARKS				
	A	B	Main	Case	Case	Disk	Pump Inlet	Pump Outlet	Case Drain	TV Outlet	Heat Exchanger Inlet	Heat Exchanger Outlet									
12.0							12.0 hours on pump for test stand refinement.										Stage I - Test Start.				
12.2																	Sample Taken (Stage I - 0.2 hrs.)				
14.7																	Manual Shutdown.				
14.7																	Test Restart.				
14.9																	Auto Shutdown @ 14.9 hrs., cause unknown. Test Restart.				
16.3			50.27		3.30			180	189		222	209		83	104						
18.0																					
19.0			50.30		3.40			180	188		222	209		83	104						
21.0			50.30		3.40			178	187		220	208		84	104						
24.3			49.60		3.40			179	188		220	208		87	107						
27.5			49.90		3.40			178	187		219	207		86	107						
27.5																	Sample Taken (Stage I - 15.5 hrs.)				
31.2			50.20		3.50			179	188		220	209		89	109						
33.9			50.20		3.50			179	189		220	209		89	110						
36.6																	Manual Shutdown @ 36.6 - Computer problem.				
36.6																	Test Restart				
38.0			49.90		3.30			178	187		219	207		87	108						
40.5			50.10		3.40			178	187		219	207		89	109						
42.0			50.10		3.40			177	187		219	207		87	108						
42.4																	Sample Taken (Stage I - 30 hrs.)				
42.5																	Test stopped for inspection after stage I				
43.2																	Stage II - Test Start				
44.2																	Sample Taken (Stage II - 1 hr.)				
44.7			50.20		3.50			205	214		244	234		122	144						
45.5			49.70		3.50			211	220		249	239		130	150						
48.1			49.60		3.60			214	223		252	242		136	155						
49.5																	Sample Taken (Stage II - 6.3 hrs.)				
53.1			51.20		3.80			207	216		246	236		127	147						
56.1			50.10		3.80			211	220		249	239		134	153						
57.9			49.42		3.80			211	220		249	240		134	154						
58.3																	Sample Taken (Stage II - 15.1 hrs.)				
59.5																	Broken wire repaired - Main flow update				
60.0			49.45		3.80			208	219		248	238		134	153						
62.0			49.75		3.80			210	220		248	239		134	154						

PUMP TEST NO. 33

TEST PUMP: MODEL Vickers PV3-300-7B										TEST FLUID: MIL-H-5606F										
PUMP TEST DATA FOR AIRCRAFT HYDRAULIC FLUID										WL/MLBT, WPAFB PUMP TEST STAND NO. 1										
MLO 92-144																				
A- Throttling Valve Open																				
B- Throttling Valve Closed																				
Date	Time	Cell Temp. (F)	Test Hrs. (as on the counter)	Total Flow (Gallons)			Reserv. Fluid Level (mm)	Total Seal Leakage (ml)	Speed (RPM)		Torque (in-lb)		Motor Current (amps)	Pressure Drop (PSI)			Pump Inlet Pressure (psig)		Pump Outlet Pressure (psig)	
				Main	Case	Disc			A	B	A	B		Main Filter 1	Case Filter	Deq. Corp.	A	B	A	B
29-Jan-93	1302	86	65.5	157,108	11,028		131.07	415	5,215		1746		161	26	3.6	77	7	90		4,102
29-Jan-93	1812	81	70.7	172,598	12,186		130.90	480	5,215		1727		161	25	3.3	73	7	96		4,109
29-Jan-93	2016	81	72.8	178,797	12,674		130.90	500	5,212		1726		161	24	3.2	75	7	90		4,104
29-Jan-93	2040		73.2																	
29-Jan-93	2042		73.2	179,997	12,768															
17-Feb-93	0905		76.4																	
17-Feb-93	0917		76.6																	
17-Feb-93	0930		76.7																	
17-Feb-93	1006	83	78.3	193,369	13,854			500	5,230		1734		163	23	2.8	85	7	94		4,078
17-Feb-93	1145	85	78.9	195,333	14,028			500	5,230		1731		163	23	2.7	86	8	91		4,072
17-Feb-93	1430	87	81.6	203,566	14,762			500	5,240		1721		161	22	2.4	88	8	93		4,071
17-Feb-93	1536		82.7																	
17-Feb-93	1710	88	84.3	211,643	15,490			500	5,240		1729		161	23	2.0	89	8	93		4,070
17-Feb-93	2015	91	89.4	227,216	16,906				5,245		1743		162	23	1.4	92	8	93		4,070
18-Feb-93	0015		91.4																	
18-Feb-93	0500	93	96.2	247,478	18,760			500	5,245		1745		162	23	0.7	95	8	92		4,069
18-Feb-93	0805	90	99.2	256,652	19,620				5,240		1728		160	23	0.3	98	8	91		4,065
18-Feb-93	1422	91	105.6	275,677	21,424				5,240		1725		160	22	-0.1	98	8	94		4,064
18-Feb-93	1445		106.0	276,964	21,544															
19-Feb-93	0900		106.0																	

* Static Reading (Offset) : During Stage I & Stage II = 3.0 psi.; Before Stage III = 2.6 psi.; After Stage III = 0.1 psi.

** Static Reading (Offset) During the Whole Test = -7.0 psi.

*** Static Reading (Offset) During the Whole Test = -4.0 psi.

TEST PUMP : MODEL Vickers PV3-300-7B										PUMP TEST DATA FOR AIRCRAFT HYDRAULIC FLUID										TEST FLUID :									
S/N: MX 490659B										WU/MLBT, WPAFB PUMP TEST STAND NO. 1										Mil- H-5606F MLO 92-144									
Test Hrs.		Coolant Flow (GPM)		Flow Rate (GPM)				Pump				Fluid Temperature (F)				Coolant Temperature (F)				REMARKS									
				Main		Case		Disk		Pump Inlet		Pump Outlet		Case Drain		TV Outlet		Heat Exchanger Inlet						Heat Exchanger Outlet					
A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B								
65.5		50.65		3.80				208		217		246		131				151											
70.7		49.90		3.90				209		218		246		134				154											
72.8		49.90		3.90				210		219		248		137				156											
73.2																													
73.2																													
76.4																													
76.6																													
76.7																													
78.3		50.25		4.40				247		257		281		183				203											
78.9		50.07		4.50				249		259		284		187				206											
81.6		50.12		4.60				250		259		283		187				208											
82.7																													
84.3		50.14		4.60				249		258		283		187				208											
89.4		50.64		4.70				249		257		282		187				209											
91.4																													
96.2		50.80		4.70				249		258		282		188				211											
99.2		50.00		4.80				249		259		283		191				213											
105.6		50.00		4.80				251		261		285		195				215											
106.0																													
106.0																													

Three samples taken : 1) Main return line, 2) Heat exch. inlet line, 3) Pump case drain after removing pump.

Appendix D

Raw Data for Pump Test 34

with MIL-H-87257

TEST FLUID: Mil-H-87257 (Royco)
MLO 92-11, MLO-92-142C

TEST FLUID:

PUMP TEST DATA FOR AIRCRAFT HYDRAULIC FLUID
WMLBT, WPAFB PUMP TEST STAND NO. 1

MODEL **Vickers PV3-300-7B**
S/N : **MX 490651B**

TEST PUMP : MODEL

S/N : MX 490651B

A= Throttling Valve Open

B- Throttling Valve Closed

B- Throttling Valve Closed																					
Date	Time	Test Cell Temp. (F)	Test Hrs. (as on the counter)	Total Flow (Gallons)		Reserv. Fluid Level (mm)	Total Seal Leakage (ml)	Speed (RPM)		Torque (in-lb)		Motor Current (amps)	Pressure Drop (PSI)				Pump Case Outlet Pressure (psig)	Pump Inlet Pressure (psig)		Pump Outlet Pressure (psig)	
				Main	Case			A	B	A	B		Main Filler 1	Case Filler Pressure (psi)		Case Filter					
														inlet	outlet			A	B		
25-Mar-93	0937		0.0					A	B	A	B		ΔΔ	A	B	inlet	outlet	A	B	A	B
25-Mar-93	0943		0.1																		
25-Mar-93	0955		0.3																		
31-Mar-93	0945		0.3																		
31-Mar-93	1030	75	1.0	2387	156			5230			1731	168	20	92	96	0			92		4194
31-Mar-93	1305		3.6																		
31-Mar-93	1338		3.6																		
31-Mar-93	1400	76	3.8	10885	758	131.94		5210			1734	164	21	93	97	0			93		4193
31-Mar-93	1605	78	6.1																		
31-Mar-93	1802	78	9.0	26111	1798	131.75		5206			1730	160	20	95	99	1			95		4192
31-Mar-93	2030	78	10.4	30456	2084	131.75		5208			1745	161	22	96		1			95		4190
31-Mar-93	2100		11.0																		
31-Mar-93	2110		11.2																		
1-Apr-93	2300		12.9	37175	2560	131.75		5220			1726	160	20	92	96	0			92		4184
1-Apr-93	0125		15.3																		
1-Apr-93	0200	77	15.9	46175	3182			5220			1739	161	21	92	96	1			91		4182
1-Apr-93	0500	76	18.9	55063	3798	131.56	20	5220			1726	160	21	94	97	1			93		4185
1-Apr-93	0710	76	21.1	61416	4236			5220			1721	160	21	94	97	1			93		4186
1-Apr-93	0900	76	22.9	66927	4618	131.56	20	5220			1719	160	21	93	97	1			92		4184
1-Apr-93	0912		23.1																		
2-Apr-93	0834	68	23.1																		
2-Apr-93	0844		23.3																		
2-Apr-93	0855		23.3																		
2-Apr-93	1035	76	25.0	72705	5016	132.75	25	5230			1721	161	21	92	96	1			92		4183
2-Apr-93	1136	77	26.0	75741	5230			5230			1726	160	21	92	96	1			92		4184
2-Apr-93	1136	77	26.0	75741	5230			5230			1721	160	21	93	96	1			91		4184
2-Apr-93	1248	77	27.2	79354	5482			5230			1721	160	21	92	96	1			92		4183
2-Apr-93	1414	78	28.6	83586	5774			5230			1722	160	21	92	96	1			92		4183
2-Apr-93	1547	77	30.2	88261	6098	132.25	30	5230			1715	160	21	91	95	1			90		4178
2-Apr-93	1555		30.3																		
2-Apr-93	1555		30.3																		
14-Apr-93	0848		30.3																		
14-Apr-93	0912		30.7																		
14-Apr-93	0920		30.7																		
14-Apr-93	0926		30.8																		

A Static Reading (Offset) During the Whole Test = -9.0 psi.

Static Reading (Offset) During the Whole Test = 6.0 psi.

PUMP TEST NO. 34

TEST PUMP: MODEL Vickers PV3-300-7B										TEST FLUID : Mil- H-87257 (Royco) MLO 92-11, MLO-92-142C									
SN: MX 490651B										PUMP TEST DATA FOR AIRCRAFT HYDRAULIC FLUID W/LM/LBT, WPAFB PUMP TEST STAND NO. 1									
A= Throttling Valve Open B= Throttling Valve Closed																			
Test Hrs.	Coolant Flow (GPM)		Flow Rate (GPM)						Pump				Fluid Temperature (F)				Coolant Temperature (F)		REMARKS
	A	B	Main	A	B	Case	Disk		Inlet	A	B	A	Pump Inlet	Pump Outlet	Case Drain	TV Outlet	Heat Exchanger Inlet	Heat Exchanger Outlet	
0.0																			Stage I - Test Start
0.1																			Sample Taken (Stage I-0.1 hrs.).
0.3																			Manual Shutdown (Cooling water leak).
0.3																			Test Restart.
1.0			49.8			3.6			181				190		219	209	83	124	
3.6																			
3.6																			
3.9			49.8			3.5			181				191		216	210	83	126	Auto Shutdown (Reason Unknown).
6.1																			Test Restart.
9.0			50.0			3.4			181				190		216	209	83	124	Sample Taken (Stage I-6.1 hrs.).
10.4			50.3			3.4			181				190		217	209	84	123	
11.0																			
11.2																			Auto Shutdown (Operator error while changing warning settings).
12.9			49.9			3.5			181				190		212	209	84	124	Test Restart
15.3																			
15.9			50.2			3.5			181				190		213	210	84	124	Sample Taken (Stage I-15.3 hrs.).
18.9			49.8			3.5			181				190		212	209	84	124	
21.1			49.7			3.5			181				190		212	209	84	123	
22.9			49.7			3.5			181				190		212	209	84	124	
23.1																			Manual Shutdown.
23.1																			Test Restart.
23.3																			Auto Shutdown (Reason Unknown).
23.3																			Test Restart.
25.0			49.7			3.5			181				190		218	209	83	124	
26.0			49.8			3.5			181				190		216	209	83	123	
27.2			49.7			3.5			181				190		218	209	82	124	
28.6			49.8			3.5			180				190		218	209	82	124	
30.2			49.6			3.4			179				189		216	208	82	122	
30.3																			Sample Taken (Stage I-30.3 hrs.).
30.3																			Manual Shutdown - Stage I Completed - Pump Inspected.
30.3																			Stage II - Test Start.
30.7																			Auto Shutdown (Reason Unknown).
30.7																			Test Restart.
30.8																			Sample Taken (Stage II-30.8 hrs.).

* At pump case outlet.

** At pump case filter inlet (after case flow heat exchanger; before inlet to case filter).

PUMP TEST NO. 34

TEST FLUID:
Mil-H-87257 (Royco)
MLO 92-11, MLO-92-142C

PUMP TEST DATA FOR AIRCRAFT HYDRAULIC FLUID
W/LMLBT, WPAFB PUMP TEST STAND NO. 1

TEST PUMP: MODEL Vickers PV3-300-7B
S/N : MX 490651B

A- Throttling Valve Open
B- Throttling Valve Closed

Date	Time	Test Coil Temp. (F)	Test Hrs. (as on the counter)	Total Flow (Gallons)		Reserv. Fluid Level (mm)	Total Seal Leakage (ml)	Speed (RPM)		Torque (in-lb)		Motor Current (amps)		Pressure Drop (PSI)		Pump Case Outlet Pressure (psig)	Pump Inlet Pressure (psig)		Pump Outlet Pressure (psig)
				Main	Case			A	B	A	B	A	B	Main Filter 1	Case Filter Pressure (psi)		A	B	
14-Apr-93	1045	78	32.1	93607	6526	131.75		5218		1730		162		16	93	136	92		4161
14-Apr-93	1404	80	35.4	103369	7310			5218		1712		159		16	92	138	92		4161
14-Apr-93	1455		36.3																
14-Apr-93	1730	83	38.9	113726	8134	131.68		5217		1725		160			96	144	96		4161
14-Apr-93	2055	82	44.3	129786	9404	131.56		5215		1746		161			94	144	94		4160
15-Apr-93	0000		45.4																
15-Apr-93	0342	82	49.1	144339	10546	131.44	50	5215		1727		160		17	96	144	95		4160
15-Apr-93	0555	82	51.3	150997	11066	131.44	50	5215		1726		160		17	96	144	96		4161
15-Apr-93	0855	80	54.3	159951	11776	131.44	50	5215		1716		160		17	94	141	94		4160
15-Apr-93	1245	81	58.2	171531	12686	131.44	50	5215		1752		162		17	95	143	95		4157
15-Apr-93	1448	81	60.2	177584	13162	131.41	50	5217		1726		160		17	94	140	94		4159
15-Apr-93	1455		60.3																
15-Apr-93	1458		60.3																
26-Apr-93	1355		60.4																
26-Apr-93	1413		60.7																
26-Apr-93	1420		60.7																
26-Apr-93	1435		60.9																
26-Apr-93	1530	85	61.8	181904	13522			5230		1721		162		14	92		93		4127
26-Apr-93	1720		63.6		14494														
26-Apr-93	1825	86	64.7	190690		132.38	60	5230		1708		159		14	92		91		4119
26-Apr-93	1930		65.9		15736														
26-Apr-93	2025		66.7																
26-Apr-93	2125		67.7	189650	16708	132.19	70	5230		1704		159		14	92		92		4119
26-Apr-93	2310	81	69.5	204935	17178	132.17	70	5230		1710		160		15	98		97		4124
27-Apr-93	0018		70.8																
27-Apr-93	0040		70.8																
27-Apr-93	0130		71.5																
28-Apr-93	0638		71.6																
28-Apr-93	0702		72.0																
28-Apr-93	0704		72.0																
28-Apr-93	0823		73.3																
28-Apr-93	1013		73.3																
28-Apr-93				Test stopped & restarted several times. Inlet & outlet T/C fluctuating (opening & closing). Thought excessive vibrations may be the cause. (See next page same line).															
30-Apr-93	0955		74.8																
30-Apr-93	1006		75.0																
30-Apr-93	1012		75.0																
30-Apr-93	1055	87	75.7	221105	18574			5230		1712		163		14	92		92		4126

Δ Static Reading (Offset) During the Whole Test = -9.0 psi.
ΔΔ Static Reading (Offset) During the Whole Test = -6.0 psi.

PUMP TEST NO. 34

TEST PUMP : MODEL										Vickers PV3-300-7B										PUMP TEST DATA FOR AIRCRAFT HYDRAULIC FLUID										TEST FLUID :									
SN: MX 400651B																				WMLBT, WPAFB PUMP TEST STAND NO. 1										MIL- H-87257 (Royco) MLO 92-11, MLO-92-142C									
A= Throttling Valve Open B= Throttling Valve Closed																																							
Test Hrs.	Coolant Flow (GPM)		Flow Rate (GPM)						Pump Inlet				Pump Outlet				Case Drain				TV Outlet		Heat Exchanger Inlet		Heat Exchanger Outlet		REMARKS												
	A	B	Main	A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B														
32.1			49.8	4.1				209	222	248	241			136																									
35.4			49.5	4.0				209	221	247	239			134																									
36.3																																							
38.9			49.9	4.0				212	224	250	242			139																									
44.3			50.5	4.0				210	222	248	240			134																									
45.4																																							
49.1			49.9	4.0				212	224	250	242			139																									
51.3			49.9	4.0				212	224	249	242			138																									
54.3			49.6	4.0				212	224	249	242			139																									
58.2			50.8	4.0				213	225	250	243			139																									
60.2			49.9	4.0				211	223	248	241			137																									
60.3																																							
60.3																																							
60.4																																							
60.7																																							
60.7																																							
60.9																																							
61.8			49.9	4.6				248	259	282	276			195																									
63.6																																							
64.7			49.8	Inop.				253	264	287	271	281		203																									
65.9																																							
66.7																																							
67.7			49.7	4.5				253	264	287	271	281		203																									
69.5			49.9	4.5				252	264	286	271	280		202																									
70.8																																							
70.8																																							
71.5																																							
71.6																																							
72.0																																							
72.0																																							
73.3																																							
73.3																																							
Opened pump for inspection. Looks good. Fixed both T/C leads.																																							
74.8																																							
75.0																																							
75.0																																							
75.7			49.7	4.6				249	255	282	266	276		196																									

* At pump case outlet.

** At pump case filter inlet (after case flow heat exchanger, before inlet to case filter).

PUMP TEST NO. 34

TEST PUMP: MODEL Vickers PV3-300-7B										TEST FLUID: Mil-H-87257 (Royco) MLO 92-11, MLO-92-142C													
PUMP TEST DATA FOR AIRCRAFT HYDRAULIC FLUID WJALBT, WPAFB PUMP TEST STAND NO. 1																							
A= Throttling Valve Open B= Throttling Valve Closed																							
Date	Time	Test Cell Temp. (F)	Test Hrs. (as on the counter)	Total Flow (Gallons)		Reserv. Fluid Level (mm)	Total Seal Leakage (ml)	Speed (RPM)		Torque (in-lbf)		Motor Current (amps)		Pressure Drop (PSI)				Pump Case Outlet Pressure (psig)	Pump Inlet Pressure (psig)		Pump Outlet Pressure (psig)		
				Main	Case			A	B	A	B	A	B	Inlet	outlet	A	B		A	B			
																					ΔΔ	Δ	Δ
30-Apr-93	1330	87	78.3	228822	19252	133.10	90	5230		1714		160		15		89	90			90		4119	
30-Apr-93	1400		78.8																				
30-Apr-93	1718	86	82.1	240198	20238	133.00	90	5230		1715		160		14		96	97			96		4124	
30-Apr-93	2100	83	85.8	251377	21202	133.00	100	5230		1715		160		15		96	97			97		4122	
30-Apr-93	2233	82	87.3	256039	21600	133.00	105	5230		1720		161		14		97	92			97		4122	
1-May-93	0137	81	90.4	265405	22396	132.94	110	5230		1737		162		15		97	98			97		4123	
1-May-93	0437	79	93.4	274524	23170	132.88	115	5230		1700		160		14		96	97		146	96		4121	
1-May-93	0500		93.8																				
1-May-93	0506		93.9	275877	23286																		

Δ Static Reading (Offset) During the Whole Test = -9.0 psi.

ΔΔ Static Reading (Offset) During the Whole Test = -6.0 psi.

PUMP TEST NO. 34

TEST PUMP: MODEL Vickers PV3-300-7B										PUMP TEST DATA FOR AIRCRAFT HYDRAULIC FLUID										TEST FLUID :										Mil- H-87257 (Royco)										MLO 92-11, MLO 92-142C									
S/N: MX 490651B										WL/MLBT, WPAFB PUMP TEST STAND NO. 1																																							
A= Throttling Valve Open																																																	
B= Throttling Valve Closed																																																	
Test Hrs.	Coolant Flow (GPM)		Flow Rate (GPM)				Fluid Temperature (F)				Coolant Temperature (F)				REMARKS																																		
	A	B	Main	Case	A	B	A	B	Pump Inlet	Pump Outlet	Case Drain	TV Inlet	TV Outlet	Heat Exchanger Inlet	Heat Exchanger Outlet	A	B	A	B	A	B					A	B	A	B																				
78.3			50.0	4.4					251	257	284	270	278			202																		Sample Taken (Stage III-78.8 hrs.)															
78.8																																																	
82.1			50.2	4.4					251	257	285	270	279			200																		224															
85.8			50.2	4.4					253	259	286	271	281			202																		226															
87.3			50.3	4.4					251	257	285	270	279			200																		224															
90.4			50.8	4.4					253	258	286	271	280			202																		226															
93.4			49.7	4.4					251	257	285	270	279			200																		224															
93.8																																		Sample Taken (Stage III-93.8 hrs.)															
93.9																																		Manual Shutdown - Stage III Completed - Pump Inspected															

* At pump case outlet

** At pump case filter inlet (after case flow heat exchanger; before inlet to case filter).